







- NOTES:**
- 1- CURB FACE TO BE 8" UNLESS OTHERWISE INDICATED.
 - 2- CAMPBELL CASTING PATTERN NO. 2619, "BICYCLE SAFE GRATE" OR APPROVED EQUIVALENT.
 - 3- LADDER RUNGS SHALL BE POLYPROPYLENE AS PER DETAIL.
 - 4- WHERE INLETS ARE GREATER THAN 8' DEEP, DOUBLE BLOCK WALLS ARE REQUIRED.




INLET TYPE "B"



MANHOLE, 4' DIAMETER




SECTION B-B



MANHOLE, 5' DIAMETER

PRECAST MANHOLE RISER JOINT DETAIL

STORM SEWER MANHOLES




FRONT VIEW

PROFILE


- NOTE:**
- SEE PROFILE FOR REINFORCED STEEL DETAIL

REINFORCED CONCRETE STEP DETAIL



TYP. STORM SEWER MANHOLE FRAME & COVER

- NOTES:**
- 1- IF WATERTIGHT MANHOLE FRAMES & COVERS ARE REQUIRED, THEY SHALL BE AS MFG. BY "CAMPBELL FOUNDRY CO.", PATTERN NO. 1536, TYPE "A" OR APPROVED EQUIVALENT.
 - 2- WHERE WATERTIGHT MANHOLE FRAME & COVER ARE NOT REQUIRED, THE MANHOLE COVER AND FRAME SHALL BE OF THE HEAVY HIGHWAY TYPE, WITH THE CIRCULAR FLARED TYPE FRAME AND ROUND FLANGE. THE COVER SHALL BE PERFORMED WITH A MINIMUM OF SIX 3/4" HOLES.
 - 3- TO BE USED ON STREETS "CAMPBELL FOUNDRY CO." PATTERN NO. 1202 OR EQUIVALENT.
 - 4- TO BE USED OUTSIDE OF STREET R. O. W. "CAMPBELL FOUNDRY CO." PATTERN NO. 1486 OR EQUIVALENT.




NOTE:

UNDERDRAIN SHALL BE CONNECTED TO EACH DOWN STREAM DRAINAGE STRUCTURE AND SHALL BE CAPPED AT THE UPSTREAM END


TYP. PIPE BEDDING STORM SEWER

PIPE DIAMETER	"A"	"B"	"C"
15"	9 3/4"	15 3/4"	43 1/2"
18"	11 1/2"	17 1/2"	47"
24"	15"	21"	54"
30"	18 1/2"	24 1/2"	61"
36"	22"	28"	68"
42"	25 1/2"	31 1/2"	75"
48"	29"	35"	82"




PLAN

- NOTES:**
- 1- CASTING SHALL BE "CAMPBELL FOUNDRY CO.", PATTERN NO. 3425 "BICYCLE SAFE GRATE" OR EQUIVALENT.
 - 2- LADDER RUNGS SHALL BE POLYPROPYLENE.
 - 3- WHERE INLETS ARE GREATER THAN 8' DEEP, DOUBLE BLOCK WALLS ARE REQUIRED.




PLAN

- NOTES:**
- 1- LADDER RUNGS SHALL BE POLYPROPYLENE.
 - 2- WHERE MANHOLE IS GREATER THAN 8' DEEP, DOUBLE BLOCK WALLS ARE REQUIRED.




INLET TYPE "A"

- NOTES:**
- 1- CAMPBELL CASTING PATTERN NO. 3433 FOR "STREAM FLOW GRATING" AND NO. 3408 FOR "BICYCLE SAFE GRATING" OR APPROVED EQUIVALENT.
 - 2- LADDER RUNGS SHALL BE POLYPROPYLENE AS PER DETAIL.
 - 3- SPECIAL DESIGNS SHALL BE PROVIDED FOR INLETS WITH PIPE SIZES GREATER THAN 21" DIAMETER.
 - 4- WHERE INLETS ARE GREATER THAN 8' DEEP, DOUBLE BLOCK WALLS ARE REQUIRED.




SECTION "C-C"

BICYCLE SAFE GRATE




SECTION "B-B"




INLET TYPE "E"

SECTION "A-A"



INLET TYPE "E"

SECTION "B-B"



TOWNSHIP of WOODBRIDGE

DIVISION of ENGINEERING

ONE MAIN STREET, WOODBRIDGE, NEW JERSEY 07095
ROBERT A. SIMCSAK
MUNICIPAL ENGINEER

(732) 602-6047
JAMES E. MCGREEVEY
MAYOR

GENERAL CONSTRUCTION DETAILS

DESIGNED:	SITUATED IN:	WOODBRIDGE TOWNSHIP	DATE:
DRAWN: M. J. F.	MIDDLESEX COUNTY	NEW JERSEY	SOURCE:
CHECKED: B. PATEL			N. T. S.
APPROVED: R. A. S.			FILE NO.:
STA. to STA.			CONTRACT NO.:
BOOK:			DRAWING NO.:
PAGES:			SHEET
B. M.:			2 OF 6

SCOTT LEE THOMPSON

MUNICIPAL ENGINEER
N.J.P.E. Lic. No. 29141



- 2- 1/2" EXPANSION JOINT EVERY 24'. STEEL SEPARATORS SHALL BE USED WITH THE FORMS AT 12' INTERVALS AND A FALSE JOINT SHALL BE TOOLED IN EVERY 4'.



DRIVEWAY REPLACEMENT DETAIL



MIX NUMBERS IN ACCORDANCE WITH NEW JERSEY DEPARTMENT
OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD
AND BRIDGE CONSTRUCTION



DRIVEWAY REPLACEMENT DETAIL



DRIVEWAY REPLACEMENT DETAIL



- 1- FRAME AND COVER TO BE CAMPBELL
FOUNDRY CO., PATTERN NUMBER 2801 OR EQUAL
- 2- A PRECAST UNIT MAY BE INSTALLED AT THE
OPTION OF THE CONTRACTOR. WALL'S SHALL
BE 6" THICK, PRICE PER UNIT SHALL REMAIN
THE SAME.

UNDERDRAIN HANDHOLE DETAIL



- 1- CONCRETE TO TEST 4500 P. S. I. MINIMUM ON 28 DAY TEST AIR ENTRAINMENT 4% TO 7%. SLUMP TO BE 5" MAXIMUM.
- 2- SEE DETAILS FOR HANDICAPPED RAMP.



TYPICAL 9" X 20" CURB DETAIL



ALL CONCRETE TO BE
4500 P. S. I. MIN

SECTION WITH SIDEWALK



ALL CONCRETE TO BE
4500 P. S. I. MIN

SECTION WITHOUT SIDEWALK




- 1- TWO (2) AND THREE (3) STEP INSTALLATION SHALL BE IN ACCORDANCE WITH CONCRETE STEP DETAIL.
- 2- FOUR (4) STEPS OR GREATER SHALL BE IN ACCORDANCE WITH REINFORCED CONCRETE STEP DETAIL.



THE CROWN OFF ALL PAVEMENT SHALL BE
AS INDICATED ON THE CROSS SECTIONS

TYPICAL PAVEMENT DETAIL



TOWNSHIP of WOODBRIDGE
DIVISION of ENGINEERING

ONE MAIN STREET, WOODBRIDGE, NEW JERSEY 07095
ROBERT A. SIMICSAK
MUNICIPAL ENGINEER

(732) 602-6047
JAMES E. McGREEVEY
MAYOR

GENERAL CONSTRUCTION DETAILS

DESIGNED:	SITUATED IN	WOODBIDGE TOWNSHIP	DATE:
DRAWN: M. J. F.	MIDDLESEX COUNTY	NEW JERSEY	SCALE:
CHECKED: B. PAIEL			N. T. S.
APPROVED: R. A. S.			
STA. TO STA.			FILE NO.:
BOOK:			CONTRACT NO.:
PAGES:			DRAWING NO.:
B. M.:			SHEET
	SCOTT LEE THOMPSON	DATE	1 OF 6
	MUNICIPAL ENGINEER		
	N.J.E.C. NO. 2814		

NOTES:

- 1- LADDER RUNG TO BE AS MANUFACTURED BY M. A. INDUSTRIES OR APPROVED EQUIVALENT.
- 2- IN PRECAST MANHOLES, STEPS SHALL BE DRIVEN INTO WET CONCRETE WALL DURING MANUFACTURE

SECTION "A-A"

NOTES:

- 1- STRAP ON SADDLE TO BE AS MANUFACTURED BY "PIONEER" OR APPROVED EQUIVALENT.
- 2- STRAP ON SADDLE TO BE USED ON EXISTING MAINS ONLY WHERE A WYE BRANCH LATERAL CONNECTION IS NOT AVAILABLE.

STRAP ON SADDLE DETAIL

NOTE:
TYPE OF CONNECTION TO BE
AS DIRECTED BY THE ENGINEER


TYPICAL LATERAL CONNECTION WITH RISER

SLOPED RISE

NOTES:

- 1- FURNISH AND INSTALL COMPACTED CLAY MATERIAL FOR FULL WIDTH OF TRENCH AS APPROVED BY THE ENGINEER.
- 2- CLAY STOP SHAPE MAY BE INVERTED IF BACKFILL IS PLACED FIRST.

IMPERVIOUS TRENCH STOP



INSTALLATION

**POLYPROPYLENE LADDER
RUNG DETAIL**

PLAN

PLAN

NOTE:
MANHOLE DIAMETER SHALL BE 60" FOR MAIN SIZES GREATER THAN 18" AND LESS THAN 27", LARGER MANHOLES SHALL BE REQUIRED FOR LARGER MAINS AND FOR DEFLECTION AS APPROVED BY THE ENGINEER

SECTIONAL PLAN AND CONNECTION TO EXISTING SANITARY SEWER

SECTIONAL PLAN

SECTION "A-A"


SECTION "A-A"

**PVC SANITARY SEWER
LATERAL AND CLEANOUT**

MAXIMUM PAYMENT WIDTH			
STORM SEWER & SANITARY SEWER DEPTH			
PIPE DIA	DEPTH		
	1'-6"	5'-0"	12'-0"
8"	4'-0"	5'-0"	6'-0"
10"	4'-0"	5'-0"	6'-0"
12"	4'-0"	5'-0"	6'-0"
15"	4'-0"	5'-0"	6'-0"
18"	4'-6"	5'-0"	6'-0"
21"	4'-6"	5'-0"	6'-0"
24"	5'-0"	5'-0"	6'-0"
27"	5'-0"	6'-0"	7'-0"
30"	5'-0"	6'-0"	7'-0"
33"	5'-0"	6'-0"	7'-0"
36"	5'-0"	6'-0"	7'-0"
42"	6'-0"	6'-0"	7'-0"
48"	6'-0"	6'-0"	7'-0"

NOTE:

WITH THE EXCEPTION OF ROCK EXCAVATION, ALL COST OF EXCAVATION SHALL BE INCLUDED IN THE PRICE PER LINEAR FOOT OF PIPE. THE COST OF BACKFILLING SHALL COMPLY WITH THE PROVISIONS OF THE SPECIFICATIONS.



**DUCTILE IRON SANITARY SEWER
LATERAL AND CAST IRON CLEANOUT**

NOTES:

1- CONTRACTOR IS RESPONSIBLE FOR ULTIMATELY PROVIDING PERMANENT PAVEMENT (UNLESS OTHERWISE NOTED IN SUPPLEMENTARY SPECIFICATIONS)

NOTES:

NOTES:

1- CONTRACTOR IS RESPONSIBLE FOR ULTIMATELY PROVIDING PERMANENT PAVEMENT (UNLESS OTHERWISE NOTED IN SUPPLEMENTARY

NOTES:

**TYPICAL SANITARY SEWER
MANHOLE FRAME AND COVER**

TYPICAL TRENCH DETAIL

SECTION "A-A"

TYPICAL PRECAST CONCRETE SANITARY SEWER MANHOLE

SECTION "A-A"

TYPICAL PRECAST DROP MANHOLE

UNPAVED TRENCH REPAIR

TOWNSHIP of WOODBRIDGE DIVISION of ENGINEERING	
ONE MAIN STREET, WOODBRIDGE, NEW JERSEY 07095 ROBERT A. MCGIRAK MUNICIPAL ENGINEER	
(732) 602-6047 JAMES E. MCGREEVEY MAYOR	
GENERAL CONSTRUCTION DETAILS	

DESIGNED:	SITUATED IN	WOODBRIDGE TOWNSHIP	DATE:
DRAWN: M. J. F.	MIDDLESEX COUNTY	NEW JERSEY	SCALE:
CHECKED: B. PATEL			N. T. S.
APPROVED: R. A. S.			FILE NO.
STA. to STA.			CONTRACT NO.
BOOK:			DRAWING NO.
PAGES:			SHEET
B. M.:			3 OF 6


SCOTT LEE THOMPSON

MUNICIPAL ENGINEER
N.J.P.E. LIC. NO. 29141

NOTES:

- 1- FLOOD LIGHTS SHOULD BE PROVIDED TO MARK FLAGGER STATIONS AT NIGHT AS NEEDED
- 2- WARNING LIGHTS SHOULD BE USED TO MARK CHANNELIZING DEVICES AT NIGHT AS DETAILED IN THE NIGHT TIME OPERATIONS SECTIONS OF THE SPECIFICATIONS.
- 3- CHANNELIZING DEVICES ARE TO BE EXTENDED TO A POINT WHERE THEY ARE VISIBLE TO APPROACHING TRAFFIC.
- 4- IF ENTIRE WORK AREA IS VISIBLE FROM ONE STATION A SINGLE FLAGGER MAY BE USED.


WARNING SIGN SEQUENCE
IN OPPOSITE DIRECTION
SAME AS BELOW



MINIMUM REQUIREMENTS FOR
TEMPORARY LANE CLOSURE

NOTE:

EXCAVATIONS OR EDGES OF LIFTS WITH VERTICAK DROP-OFS OF 2" OR MORE THAT ARE TO REMAIN DURING NON-WORKING HOURS ARE TO BE RAMPED AS SHOWN. THERE WILL BE NO SEPERATE PAYMENT FOR THE CONSTRUCTION OF THE ESCAPE RAMP



ESCAPE RAMP DETAIL

TRAFFIC CONTROL COORDINATION:

- 1- PRIOR TO THE START OF CONSTRUCTION, THE ENGINEER SHALL BE NOTIFIED OF THE SINGLE SUPERVISORY LEVEL INDIVIDUAL, TRAINED IN THE PRINCIPLES OF SAFE TRAFFIC CONTROL, WHO, ALONG WITH THE DIRECTION OF THE POLICE DEPARTMENT'S TRAFFIC SAFETY DIVISION, WILL BE ASSIGNED THE RESPONSIBILITY AND AUTHORITY FOR THE IMPLEMENTATION AND MAINTENANCE OF THE TRAFFIC CONTROL.
- 2- THE PERSON ASSIGNED SHALL MAKE A CHECK OF ALL TRAFFIC CONTROL DEVICES IN USE ON THE ENTIRE PROJECT AT LEAST TWICE A DAY ON WORKING DAYS AND ONCE A DAY ON NON-WORKING DAYS. CONTRACTOR SHALL FILE THE NAME AND TELEPHONE NUMBER OF THE PERSON ASSIGNED TO PROVIDE SERVICES.

TRAFFIC CONTROL DEVICES:

- 1- TRAFFIC CONTROL DEVICES SHALL BE KEPT CLEAN AND MAINTAINED IN GOOD CONDITION INCLUDING REPLACEMENT IF LOST, STOLEN OR DAMAGED UNTIL NO LONGER REQUIRED FOR THE PROJECT. ALL TRAFFIC CONTROL DEVICES SHALL COMPLY WITH THE DETAILS SHOWN ON THE PLANS, SUPPLEMENTARY SPECIFICATIONS, THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND STANDARD DETAILS FOR TRAFFIC CONTROL DEVICES AS DEVELOPED BY THE NEW JERSEY DEPARTMENT OF TRANSPORTATION.
- 2- TRAFFIC CONTROL DEVICES SHALL ALSO BE PLACED AS DIRECTED BY THE ENGINEER TO PROVIDE TRAFFIC CONTROL FOR PERSONNEL DOING INSPECTIONS, SAMPLING, TESTING OR TAKING MEASUREMENTS REQUIRED FOR THE PROJECT.

CONSTRUCTION SIGNS:

- 1- CONSTRUCTION SIGNS SHALL BE INSTALLED BY THE CONTRACTOR AS REQUIRED BY THE POLICE DEPARTMENT AS THE FIRST ORDER OF WORK FOR CONSTRUCTION SIGNS FOR PROJECTS AND SHALL BE MAINTAINED SO AS TO PROVIDE MAXIMUM VISIBILITY AND LEGIBILITY AT ALL TIME.
- 2- WHEN CONSTRUCTION SIGNS CONFLICT WITH EXISTING SIGNS, THE EXISTING SIGN SHALL BE COVERED. WHEN CONSTRUCTION SIGNS ARE NO LONGER REQUIRED, THEY SHALL BE REMOVED. IF THEY ARE TEMPORARILY NOT REQUIRED, SUCH AS OVERNIGHT, THEY SHALL EITHER BE TEMPORARILY REMOVED OR COVERED.
- 3- EACH ADVANCE WARNING SIGN (W20-1) SHALL BE LIGHTED 24 HOURS A DAY WITH DUAL ALTERNATE FLASH HIGH INTENSITY WARNING LIGHTS OF EITHER THE STROBE OR INCANDESCENT TYPE AS SELECTED BY THE CONTRACTOR.

CONSTRUCTION STAGING PLAN:


- 1- THE CONSTRUCTION STAGING PLAN IS BASED ON THE MINIMUM REQUIREMENTS PROVIDED IN THE CURRENT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). THE CONTRACTOR SHALL WORK IN ACCORDANCE WITH THE PROVISIONS OF THE PLAN AND THE MUTCD AND SHALL ONLY DEVIATE FROM THE PLAN AFTER APPROVAL.
- 2- APPROVAL OF THE ENGINEER AND CONSENT OF THE LOCAL AUTHORITIES HAVING JURISDICTION SHALL FIRST BE OBTAINED FOR REROUTING TRAFFIC OVER DETOURS THAT ARE NOT SHOWN ON THE PLANS. ALL NECESSARY ARRANGEMENTS SHALL BE MADE WITH SUCH AUTHORITIES REGARDING THE ESTABLISHMENT, MAINTENANCE AND REPAIR OF SUCH DETOURS, THE REGULATION AND DIRECTION OF TRAFFIC THEREON, AND SIGNING. ADEQUATE DIRECTIONAL AND DETOUR SIGNS, ACCEPTABLE TO THE LOCAL AUTHORITIES, SHALL BE FURNISHED AND ERECTED AT THE LOCATIONS WHERE SUCH AUTHORITIES MAY DIRECT.
- 3- CONSTRUCTION STAGING PLANS SHALL BE USED IN CONJUNCTION WITH THE SPECIFICATIONS-SECTION 110. IF A CONFLICT ARISES BETWEEN THE PLANS AND SPECIFICATIONS, THE SPECIFICATIONS SHALL GOVERN UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- 4- ITEMS AND QUANTITIES SHOWN ARE INTENDED ONLY AS A GUIDE TO THE CONTRACTOR AND ARE SUGGESTED MINIMUMS FOR THE CLOSURE OF ONE LANE AND TWO LANES OF TRAFFIC.

SUGGESTED GENERAL SEQUENCE OF CONSTRUCTION:

- 1- PROVIDE ADVANCE NOTIFICATION TO THE LOCAL POLICE DEPARTMENT AND THE ENGINEER PRIOR TO MODIFICATION OF EXISTING TRAFFIC PATTERNS.
- 2- INSTALL 'ADVANCE WARNING' SIGNS.
- 3- ESTABLISH DETOUR ROUTES, IF AND WHERE APPROVED BY THE ENGINEER, WHERE APPLICABLE.
- 4- INSTALL TEMPORARY TRAFFIC CONTROL DEVICES AS APPLICABLE.
- 5- COMLETE INSTALLATION OF IMPROVEMENTS.
- 6- REMOVE TEMPORARY TRAFFIC CONTROL DEVICES, DETOUR SIGNS AND 'ADVANCE WARNING' SIGNS.

GENERAL NOTES:

- 1- VEHICULAR AND PEDESTRIAN TRAFFIC IS TO BE MAINTAINED OVER THE EXISTING ROADWAYS AND INTO EXISTING DRIVEWAYS WITHIN THE SCOPE OF THE PROJECT AT ALL TIMES. TRAFFIC CONTROL IS TO BE COORDINATED WITH LOCAL AUTHORITIES
 - 2- FINAL RESPONSIBILITY FOR THE INSTALLATION OF ADEQUATE PRECAUTIONS AND FOR THE PROTECTION OF THE TRAVELING PUBLIC AND HIS OWN PERSONNEL, SHALL REST WITH THE CONTRACTOR.
 - 3- ALTERNATE ONE-WAY TRAFFIC CONTROL MAY BE REQUIRED DURING CONSTRUCTION OPERATIONS. PERMISSION FOR COMPLETE STOPPAGE OF ONE DIRECTION OF TRAFFIC MUST BE OBTAINED FROM THE LOCAL POLICE AND THE ENGINEER AT LEAST THREE (3) DAYS PRIOR TO STOPPAGE. ALTERNATE ONE WAY TRAFFIC CONTROL WILL BE AFFECTED BY TWO UNIFORM TRAFFIC DIRECTORS, ONE AT EACH END OF THE WORK AREA. ALL TEMPORARY TRAFFIC LANES SHALL HAVE A MINIMUM UNIBSTRUCTED WIDTH OF 11 FEET.
 - 4- SITE FOR THE STORAGE OF EQUIPMENT AND MATERIALS DURING THE PROGRESS OF THE WORK SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.
 - 5- COMPLIANCE WITH ALL PRESCRIBED SAFETY PRECAUTIONS CONTAINED HEREIN SHALL NOT RELIEVE THE CONTRACTOR OF HIS PRIMARY RESPONSIBILITY TO TAKE ALL NECESSARY MEASURES TO PROTECT AND SAFEGUARD THE PUBLIC NOR RELIEVE HIM OF ANY RESPONSIBILITIES DESCRIBED IN THE CONTRACT AGREEMENTS
 - 6- IF THE LOCAL POLICE DEPARTMENT NOTIFIES THE CONTRACTOR OR HIS SUPERINTENDENT OR THE ENGINEER OF ANY HAZARDOUS CONDITION OR VIOLATION OF TRAFFIC CONTROL IN THE WORK AREA REGULATIONS, ALL OPERATIONS SHALL BE IMMEDIATELY DISCONTINUED AND IMMEDIATE REMEDIAL ACTION SHALL BE TAKEN TO THE SATISFACTION OF THE LOCAL POLICE BEFORE WORK IS RESUMED. ALL COSTS INCURRED AS A RESULT OF SUCH ACTION SHALL BE BORNE BY THE CONTRACTOR WITHOUT RECOURSE AGAINST THE OWNER.
 - 7- REDUCTION OF THE NUMBER OF LANES AVAILABLE FOR TRAFFIC OR REDUCTION OF EXISTING WIDTHS OF TRAVELED WAY WILL NOT BE PERMITTED UNTIL AFTER 9:00 AM AND SHALL BE REMOVED PRIOR TO 4:00 PM UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 - 8- WORK WHICH WILL INTERFERE WITH WITH TRAFFIC OR RESTRICT THE WITH OF TRAVELED WAY AVAILABLE FOR TRAFFIC SHALL NOT BE PERFORMED ON SATURDAYS, SUNDAYS OR LEGAL HOLIDAYS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 - 9- PRIOR TO BEGINNING A SEASONAL SHUTDOWN OR ANY OTHER PROLONGED WORK STOPPAGE, OR WHEN WORK IS SUSPENDED BY THE ENGINEER, ALL EXCAVATED AREAS WITHIN THE TRAVELED WAY OR ADJACENT THERETO SHALL BE BROUGHT TO A GRADE COMPATIBLE WITH THE EXISTING TRAVELED WAY OR TO FINISHED GRADE, AS APPROVED
 - 10- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE WITHIN THE PROJECT LIMITS UNTIL ACCEPTANCE. THIS MAINTENANCE SHALL CONSIST OF CONTINUOUS AND EFTECTIVE WORK PROSECUTED DAY TO DAY, WITH ADEQUATE EQUIPMENT AND FORCES TO THE END THAT THE ROADWAY IS KEPT IN SATISFACTORY CONDITION AT ALL TIMES.
 - 11- IN THE CASE OF A CONTRACT REQUIRING THE PLACING OF A COARSE UPON A COARSE OF SUBGRADE PREVIOUSLY CONSTRUCTED, THE CONTRACTOR SHALL MAINTAIN THE PREVIOUS COURSE OF SUBGRADE DURING ALL CONSTRUCTION OPERATIONS.
 - 12- THE CONTRACTOR SHALL BACKFILL ALL EXCAVATED AREAS WITHIN THE ROADWAY TO A GRADE COMPATIBLE WITH THE EXISTING TRAVELED WAY AT SUCH TIMES HE IS NOT ACTIVELY WORKING. THIS SHALL INCLUDE NIGHTS, WEEKENDS AND PERIODS OF SHUTDOWNS.
 - 13- COMPETENT, TRAINED AND UNIFORMED TRAFFIC DIRECTORS SHALL BE EMPLOYED AT EVERY POINT WHERE CONTRACTOR'S EQUIPMENT IS WORKING IMMEDIATELY ADJACENT TO, OR IS ENTERING, LEAVING OR CROSSING ACTIVE TRAFFIC LANES. TRAFFIC DIRECTORS SHALL BE EMPLOYED CONTINUOUSLY FOR THE FULL TIME SUCH CONDITIONS EXIST AS DETERMINED BY THE ENGINEER.
- THE USE OF UNIFORMED POLICE OFFICERS AS TRAFFIC DIRECTORS IS NOT A SPECIFIC REQUIREMENT OF THIS PROJECT. HOWEVER, SHOULD THEY BE DEEMED NECESSARY DUE TO IMPROPER ACTIONS OF THE CONTRACTORS TRAFFIC DIRECTORS OR SHOULD THE CONTRACTOR DESIRE THE ASISTANCE OF UNIFORMED POLICE OFFICERS AS TRAFFIC DIRECTORS, THE POLICE TRAFFIC DIRECTORS SHALL BE OFF-DUTY POLICE OFFICERS FROM WITHIN THE MUNICIPALITY WHERE THE WORK IS BEING PERFORMED. POLICE TRAFFIC DIRECTORS SHALL BE LOCATED WHERE SHOWN ON THE PLANS OR AT SPECIFIC LOCATIONS DESIGNATED BY THE POLICE DEPARTMENT OR ENGINEER DURING CONSTRUCTION HOURS. THE MUNICIPALITY SHALL BE CONTACTED IN ORDER TO OBTAIN THE SERVICES OF POLICE TRAFFIC DIRECTORS AND THE NAME, ADDRESS AND TELEPHONE NUMBER OF THEIR LOCAL REPRESENTATIVE.
- 14- THE OWNERS OF ADJOINING PROPERTIES SHALL BE GIVEN A WRITTEN NOTICE AT LEAST 3 DAYS PRIOR TO THE BEGINNING OF ANY WORK WHICH INTERFERES WITH THE OWNERS NORMAL PASSAGE.



TOWNSHIP of WOODBRIDGE
DIVISION of ENGINEERING


ONE MAIN STREET, WOODBRIDGE, NEW JERSEY 07095
ROBERT A. SIMICSAK
MUNICIPAL ENGINEER

(732) 602-6047
JAMES E. MCGREEVEY
MAYOR


GENERAL CONSTRUCTION DETAILS

DESIGNED:	SITUATED IN	WOODBRIDGE TOWNSHIP	DATE:
DRAWN: M. J. F.	MIDDLESEX COUNTY	NEW JERSEY	SCALE:
CHECKED: B. PATEL			N. T. S.
APPROVED: R. A. S.			FILE NO.:
STA. to STA.			CONTRACT NO.:
BOOK:			DRAWING NO.:
PAGES:			SHEET 6 OF 6
B. M.:			


SCOTT LEE THOMPSON
MUNICIPAL ENGINEER
N.J.P.E. LIC. NO. 29141




DETAIL "A"




CURB RAMP-TYPE 1



DETAIL "B"




CURB RAMP-TYPE 2




NOTE:
CURB RAMP OPENING TO BE FLUSH WITH ROADWAY PAVEMENT

SECTION "A-A"




CURB RAMP-TYPE 3




NOTE:
4' WIDE OPENING TO BE FLUSH WITH ROADWAY PAVEMENT


SECTION "B-B"




ISLAND WALKWAY OPENING AT INTERSECTIONS



SECTION THROUGH CURB RAMP




DETAIL OF DROPPED CURB AND CRADLE




DETAIL "C"

CURB RAMP TREATMENT-GRASS BUFFER STRIP 4' MINIMUM SIDEWALK LANDING AREA



SECTION "C-C"



DETAIL "D"


CURB RAMP TREATMENT-LIMITED R. O. W. WHEN "X" IS 6 FEET OR LESS

GENERAL NOTES:

- 1- LANDING AREA, APPROACH SIDEWALK TRANSITIONS AND CURB RAMP SHALL BE KEPT CLEAR OF OBSTRUCTIONS.
- 2- WHERE A GRASS BUFFER STRIP EXISTS AT A CURB RAMP TYPE 1 OR 2 LOCATION, THE FLARED SIDE SHOULD BE ALTERED AS SHOWN IN 'DETAIL C'.
- 3- CURB (DROPPED CURB) GUTTERLINE TO BE FLUSH WITH ROADWAY PAVEMENT A MINIMUM OF 4' AT ALL CURB RAMPS, EXCEPT THAT THE 'DETAIL D' SHALL BE A MINIMUM OF 5 FEET.
- 4- FOR CURB RAMP TYPE 3, IF A GRASS BUFFER DOES NOT EXIST, SLOPE CURB TO EQUAL SLOPE OF ADJACENT CURB RAMP.
- 5- SIDEWALK AND CURB RAMP WITHIN AREA ENCLOSED BY HEAVY LINES, TO BE PAID FOR AS CONCRETE SIDEWALK OF THE APPROPRIATE ADJACENT THICKNESS.
- 6- CURB AND HEADER WITHIN AREA ENCLOSED BY HEAVY LINES TO BE PAID FOR AS VERTICAL CURB OF THE APPROPRIATE ADJACENT SIZE AND KIND.
- 7- WHERE THE DISTANCE FROM THE GUTTER LINE TO THE OUTSIDE EDGE OF SIDEWALK IS 6 FEET OR LESS AT A CURB RAMP TYPE 1 OR 2 LOCATION, THE FLARED SIDE SHOULD BE ALTERED AS SHOWN IN 'DETAIL D'.
- 8- THE PUBLIC SIDEWALK CURB RAMP DELINEATION (SHADED AREA) SHALL BE SAFETY RED IN COLOR.
- 9- CROSSWALKS AND STOP LINES MAY BE MARKED OR UNMARKED, SEE PLANS.

PUBLIC SIDEWALK CURB RAMPS

 TOWNSHIP of WOODBRIDGE DIVISION of ENGINEERING ONE MAIN STREET, WOODBRIDGE, NEW JERSEY 07095 ROBERT A. SIMICSAK MUNICIPAL ENGINEER		(732) 602-6047 JAMES E. MCGREEVEY MAYOR
GENERAL CONSTRUCTION DETAILS		
DESIGNED: DRAWN: M. J. F. CHECKED: B. PATEL APPROVED: R. A. S. STA. to STA. BOOK: PAGES: B. M.:	SITUATED IN MIDDLESEX COUNTY NEW JERSEY DATE:	SCALE: N. T. S. FILE NO.: CONTRACT NO.: DRAWING NO.: SHEET 5 OF 6
SCOTT LEE THOMPSON MUNICIPAL ENGINEER N.J.P.E. LIC. NO. 28141		




NOTES:

- PIPE SECTIONS ① AND ③ VARIABLE TO BE DETERMINED IN FIELD BY ENGINEER.
- PIPE SECTION ② TO BE (UTILITY PIPE OUTSIDE DIAMETER (IN FT) + 2.0') MINIMUM LENGTH.
- CONCRETE CRADLE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 2000 P. S. I.
- RESTRAINING RODS SHALL BE UTILIZED.

WATER MAIN SIZE	RESTRAINING RODS (A-307)	CONCRETE THRUST COLLAR (2000 P.S.I. MIN.)			WATER MAIN SIZE	RESTRAINING RODS (A-307)	CONCRETE THRUST COLLAR (2000 P.S.I. MIN.)					
	NO.	SIZE (IN.)	W (FT)	H (FT)		t (FT)	NO.	SIZE (IN.)	W (FT)	H (FT)	t (FT)	
8" & LESS	2	5/8	3.5	2.5	1.5	14" TO 16"	4	5/8	3/4	5	4	2
10" TO 12"	2	5/8	4	3	1.5	18" TO 20"	4	3/4	6.5	4	2	2


UTILITY CROSSING




PERMANENT BARRICADE TYPE III MODIFIED FOR DEAD END ROADS

NOTES:


- ALL MEMBERS TO BE SOUTHERN YELLOW PINE PRESSURE TREATED CHROMATED COPPER ARSENATE (CCA) PRESERVATIVE TO 0.40 P. C. F. RETENTION IN ACCORDANCE WITH AWPJL-22 PROCESS. ALL RAILS TO BE MOUNTED AS DIRECTED BY THE ENGINEER. CONNECTIONS TO BE MADE WITH 3/4" LAG BOLTS IN COUNTERSUNK HOLES.
- FACE OF RAILS SHALL BE COVERED WITH REFLECTORIZED SHEETING, TYPE II, MEETING REQUIREMENTS OF THE NJDOT AND MUTCD. OTHER PARTS SHALL BE PAINTED WHITE. 3 COATS. MARKINGS FOR RAILS SHALL BE ALTERNATE WHITE AND RED STRIPES SLOPING DOWNWARD AT AN ANGLE OF 45° IN THE DIRECTION IN WHICH TRAFFIC MUST TURN.
- THE RED AND WHITE STRIPES SHALL BE REFLECTORIZED SO AS TO BE VISIBLE UNDER NORMAL ATMOSPHERIC CONDITIONS FROM A MINIMUM DISTANCE OF 1000 FT. WHEN ILLUMINATED BY THE LOW BEAMS OF STANDARD AUTOMOBILE HEADLIGHTS.



CONCRETE STEP DETAIL




CHAIN LINK FENCE DETAIL




LEADER OR SUMP DRAIN RECONSTRUCTION DETAIL

NOTES:

- DRAINS TO BE RECONSTRUCTED ONLY IN AREAS OF CURB REMOVAL AND REPLACEMENT AS INDICATED ON PLANS.
- PROVIDE ADAPTER IF EXISTING DRAIN IS LESS THAN 4" DIAMETER.
- IF SIDEWALK IS PROPOSED AND THERE IS NO EXISTING DRAIN, PIPE SHALL BE INSTALLED TO BACK EDGE OF SIDEWALK AND CAPPED.




TYPICAL TREE PLANTING DETAIL




TYPICAL SHRUB PLANTING DETAIL

DIMENSIONS												
DIA.	6"	8"	10"	12"	15"	18"	21"	24"	27"	30"	36"	42"
T	5"	5.5"	5.5"	6"	6"	6"	6"	7"	8"	8"	9"	10"




CONCRETE ENCASEMENT & CRADLE




PROJECT SIGN DETAIL

SECTION "A-A"


















CONNECTION OF SUMP OR LEADER DRAINS TO PROPOSED P. P. T. UNDERDRAIN



CONCRETE SUPPORT BLOCK DETAIL

 TOWNSHIP of WOODBRIDGE DIVISION of ENGINEERING ONE MAIN STREET, WOODBRIDGE, NEW JERSEY 07095 ROBERT A. SIMICSAK MUNICIPAL ENGINEER		(732) 602-6047 JAMES E. MCGREEVEY MAYOR
GENERAL CONSTRUCTION DETAILS		
DESIGNED: DRAWN: M. J. F. CHECKED: B. PATEL APPROVED: R. A. S. STA. to STA. BOOK: PAGES: S. M.:	SITUATED IN MIDDLESEX COUNTY WOODBRIDGE TOWNSHIP NEW JERSEY	DATE: SCALE: N. T. S. FILE NO.: CONTRACT NO.: DRAWING NO.: SHEET 4 OF 6
SCOTT LEE THOMPSON MUNICIPAL ENGINEER N.J.P.E. LIC. No. 29141		



TOWNSHIP of WOODBRIDGE
DIVISION of ENGINEERING

ONE MAIN STREET, WOODBRIDGE, NJ 07095
MICHAEL GELIN, PE
MUNICIPAL ENGINEER

(732) 662-6047
JOHN E. McGORMAC
MAYOR

GENERAL CONSTRUCTION DETAILS
(for ROAD OPENING & SIDEWALK PERMIT)

FILE #:

SCALE: As Shown

DRAWN BY: M.F.

CHECKED BY: Bask

DATE: April 2017

DESIGNED BY: Bask

SHEET #:

TOWN CONTRACT #:

MICHAEL GELIN, P.E.
NEW JERSEY PROFESSIONAL ENGINEER
LIC. NO. 04892800

1 of 1